

**BANK OF INDIA****Achalpur BRANCH.****QUOTACTION DOCUMENT OF FURNISHING work finishing limit 10 days.**

<b>SR NO.</b>	<b>Description Of Item</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate (in Rs.)</b>	<b>Amount (in Rs.)</b>
<b>1</b>	<b>Flooring:</b> Providing and laying of 2'X2' Vitrified Tile flooring of approved make & shade viz. RAK (IMP-OFGY) of EURO (ATHENA) over necessary leveling screed of 1:4 cement mortar (20mm thick) with proper slope wherever required including pointing of the joints with white cement and matching pigments , curing etc. complete in all respects (excluding Toilets and Non –Customer area)	<b>Sq.ft</b>			
<b>2</b>	<b>Façade of Entrance Door-Refer Dwg.no.11</b> Providing and fixing in position Aluminum composite panel Boxing with PVDF coating & LDPE core laminated Eurobond / Altobond / Alukbond Exterior Grade 4 mm thick with composite of (0.5mm - 3mm- 0.5mm)including fabrication for the same with aluminum fabrication for the same silicon sealent (Dow Corning 789) masking tape, necessary scaffolding etc. as detailed in drawing no. (11) Complete in all respects.	<b>Sq.ft.</b>	<b>90</b>		
<b>3</b>	<b>False ceiling (Armstrong)</b> Providing & fixing in position false ceiling in Armstrong 600X 600 mm X 15/16 mm Dune Supreme RH 99 Prima tile with Tegular edge framework as specified by Armstrong Co. with suspender wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutout for diffusers and light feting, taping and finishing to proper & level, including making grooves and tapes doors for A.C. unit in 18 mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edge including finishing with White Plastic Emulsion Paint etc. complete in all respect. (Note:- Only the Plane area will be measured for payment. No extra payment will be made for cutouts, grooves, moulding etc.)	<b>Sq.ft.</b>	<b>1405</b>		
<b>4.</b>	<b>False Ceiling (Gypsum Board)</b> Providing & fixing in position false ceiling in Gypboard 12mm thick for horizontal &vertical fixed over G.I. framework as				

	specified by India Gypsum Co. Ltd. including trap door for A.C. unit in 18mm thick MR Grade plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edge including finishing with white Plastic Emulsion Paint etc. complete in all respect. (Note:- Only one plan area will be measured for payment. No extra payment will be made for cutouts, grooves, moulding etc.)				
<b>5</b>	<b>Painting</b> Providing and applying White Plastic Emulsion paint of Asian Paint/ICIDulux/Berger and Sporty Yellow-X 104 shade of Royal Luxury Emulsion of Asian Paint in minimum 2 coats including scraping, opening of existing cracks, filling up of "V" cracks with epoxy expandable putty to required depths, making good weak plastered/unplastered surface with cement plaster wherever required. Item to include Plaster of Paris, primer, palti, and making good existing surface to receive new paint including cleaning on completion of painting work etc. complete in all respect.				
<b>6.</b>	<b>Entrance Door</b> Providing and fixing Entrance Door (glazed) as per drawing no. 11 in Silver Anodised aluminium door section (Jindal make) in top and bottom, glazed with 12mm thick glass of approved make with etching and frosting. Item to include floor springs, locks. All necessary hardware of Stainless Steel finished as approved by the project Consultant/Bank complete in all respects.	Sq.ft.	39		
<b>7.</b>	<b>Front Office Counter:</b> Providing and fixing in position Front Office Counter 2'-6" wide as per drawing No. (1-A, 1-B, 1-C, 1-D & 15) comprising of the following complete in all respects:- i) Working top made with 25 mm thick plywood finished with 1 mm thick laminated. Outside edge of the working top shall be provided with 1 1/4" x 1" teak wood moulding finished with melamine polish. Inside edge will be provided with 1/2" x 1" T.W. beading putty with melamine finish. ii) Vertical fascia (Apron) made with 18	Rft	15'6"		

	<p>mm thick plywood finished with 1mm thick laminated with 1 mm thick grooves at the joint of laminates of two different shade.</p> <p>iii) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18mm thick laminated with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shade of laminates.</p> <p>iv) Glazed partition above working top to be provided with 12mm thick clear glass cut to be standard shape fixed to the partition as per fixing detail and boxing with concealed S,S, finished 'D' bracket as shown in the drawing. The exposed edge of the glass shall be finished in mirror polish.</p> <p>v) 3'-10" high Boxing (10"X10") made with 18 mm thick plywood finished with 1 mm thick laminated including providing and fixing 6 mm thick square frosted glass at the height 3'-2" above finished floor level.</p> <p>vi) 1'-9" high Boxing (5"X5") made with 12 mm thick plywood finished with 1mm thick laminated.</p> <p>vii) Vertical support made with 18 mm thick plywood fished with white enamel paint.</p> <p>viii) Telescopic CPU Stand/ready made Keyboard tray shall be provided all approved model and make.</p> <p>ix) Footrest made with T.W. member of size 4"X1 1/2 " finished French polish .</p> <p>x) Drawer unit as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1 mm thick limited and all other side shall be finished with white enamel paint. The drawer will provided with handles (Stainless Still finish) and channel as per approval of the project consultant/Bank.</p> <p>xi) Boxing as per drawing made with</p>				
--	---	--	--	--	--

	<p>12mm thick plywood finished with synthetic enamel paint shall be provided below the table top for the LAN cabling/Telephone wire conducting.</p> <p>The item to include all necessary hardware and fitting in Stainless still finish, lipping to all the edge and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"X10' boxing as shown in the drawing. Necessary beading with melamine polish for fixing the glass are to be provided.</p>				
8.	<p><b>Cash Counter;</b>  Providing and fixing in the position Cash Counter 2'-9" wide as per drawing No. (2-A., 2-B, 2-C, 2-D, 2-E, 2-F) comprising of the following:</p> <ul style="list-style-type: none"> <li>i) Working top made with 25 mm thick plywood finish with 1 mm thick laminated. Outside edge of the working top shall be provided with melamine polish. Inside edge will be provided with ½"X1" T.W. beading patti with melamine polish.</li> <li>ii) Vertical facia (Apron) made with 18mm thick plywood finish with 1mm thick laminated with 1mm thick groove at the joint of laminated of two different shade.</li> <li>iii) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18mm thick plywood finish 1mm thick laminated with provision for concealed light, 1mm thick groove shall be provided at the joint of two different shade of laminated.</li> <li>iv) Glazed partition 1'-4" height above working top provided with 12mm thick toughened and frosted glass beside non-transparent film from inside fixed to partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in the drawing. The exposed edge of the glass shall be finish in mirror polish.</li> <li>v) Transaction top shall be provided with 12mm thick toughened glass</li> </ul>	Rft	11'0"		

	<p>(partly glazed partly frosted) fixed horizontally with concealed stainless still D bracket, both exposed edge (inside and outside) shall be moulded and finished in the mirror polish.</p> <p>vi) Glazed partition having height 1.0" above the transaction top (in facia) shall be provided with 12mm thick glass (clear) with cut out of 8"X4" as per drawing. The edge cut out and the top edge of the glass are to be mirror polished and to be fixed to be partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in .</p> <p>Glass (clear) above the sit to be fixed to partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in the drawing. The exposed edge shall be finished in mirror polish.</p> <p>vii) 7'-7" high Boxing (10'X10") made with 8mm thick plywood as per drawing with 1-6" horizontal extension at the top including providing and fixing 6mm thick square frosted glass at the height of 5"-11' above finished floor level.</p> <p>ix) 1'-9' high boxing (5"X5") made with 12mm thick plywood finished with 1mm thick laminated aer to be provided.</p> <p>x) Telescopic CPU Stand/ready made Keyboard tray shall be provided all approved model and make.</p> <p>xi) footrest made with T.W. member of size 4'X1 1/2" finished with French polish.</p> <p>xii) Drawer unit as per drawing shall be provided and each drawer should have vertical partition for keeping currency notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with white enamel paint. The drawer will be provided with handles (Stainless Steel finished) and channels as per approval of the Project Consultant/Bank .</p> <p>xiii) Boxing as per drawing made with 12mm thick plywood finished with</p>				
--	---	--	--	--	--

	<p>Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conducting.</p> <p>The item to include all necessary hardware and fitting in Stainless Steel finish, lapping to all edge and making provision only for electrical fitting behind the Vertical drop and also in the 10"X10" boxing as shown in the drawing . necessary beading with matching melamine polish for fixing the glass are to be provided as per drawing/as directed.</p>				
<b>9.</b>	<p><b>Solid Full Height Partition</b>  Providing and fixing in opposition solid full Height Partition in frame work including door in the 2'X2' grid (horizontally and vertically) comprising of 2"X1 1/2" T.W. section with 6mm thick plywood on the both side finished with 1mm thick laminated of the approved make and color as shown in drawing No. 17. item to include 2"X2" T.W. member for door frame. All exposed T.W. surface to be finish in melamine polish of the matching laminated color as directed including all necessary Stainless Still finish fitting/hardware, door closers, Godrej locks, and wood preservative paint etc. as per list of approved by the Project consultace/Bank complete in all respect.  (Note: In case fall ceiling, the vertical T.W. member to be fixed with pucca ceiling but the area of partition payable will be below the fall ceiling only).</p>	Sq.ft			
<b>10.</b>	<p><b>Partly Gazed full Height partition</b>  Providing and fixing in position partly glazed Full Height Partition work as show in the drawing nos. (3) &amp; (4) including door as shown in the drawing No. (13) in frame work at 2'X2' grid (Horizontally and Vertically) compromising of 2"X1 1/2" T.W. section and/or as per frame work show in the drawing with 6mm plywood on the both side finishing with 1mm thick laminated of approved shade and color as shown in the drawing. Item to include 8mm thick glass with etching and frosting as per design and 2"X2" T,W. member for door frame to take 8mm thick glass with etching and frosting.</p>	Sq.ft	279		

	<p>All exposed T.W. surface to be finished in melamine polish of matching laminated color as directed including all necessary Stainless Steel finish fitting/hardware, door closer, Godrej locks wood preservative paint etc. as per list of approved material and as approved by the project Consultance/Bank complete in all respect.</p> <p>(Note: in case of false ceiling, the vertical T.W. member to be fixed with pucca ceiling but the area of partition payable will be below the fall ceiling only).</p>				
<b>11.</b>	<p><b>Partly Glazed Partition for Cash Cabins</b>  Providing and fixing in the position 7'-7" high partly glazed partition for cash Cabins as per drawing nos. (2-A,2-B,2-C,2-D&amp;2-E) including door drawing no. (12) in frame work at 2'X2' grid (horizontally and vertically) comprising of 2"X1 1/2" T.W. section and/or as per frame work show in the drawing with 6mm plywood on the both side finishing with 1mm thick laminated of approved shade and color as shown in the drawing. Item to 8mm thick glass with etching and frosting as per design and 2"X2" T.W. member for door frame to take 8mm thick glass with etching and frosting. The door will be provided with T.W. louvers finished in melamine polish of matching laminated color. The door are also to be provided with Godrej Night Latch. Two wooden trays are also to be provided as per drawing. Necessary cutouts are to be provided in the glass and the edge of the glass cutouts are to be finished in mirror polish. All exposed T.W. surface to be finished in melamine polish of matching laminated color as directed including all necessary Stainless steel finishing/hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the project Consultant/Bank complete in all respect.</p>	Sq.ft.	396		
<b>12.</b>	<p><b>Partly Glazed Low Height Partition</b>  Providing and fixing in position partly glazed low height partition (21'2" thick) in frame work with T.W. vertical member at 2" c/c and 3 horizontal member at equal distance comprising of 2"X1 1/2" T.W. section with 6mm plywood on both side finish with 1mm</p>	Sq.ft	53		

	<p>thick laminated of the approved make and shade as shown in drawing no. (14) or (3). Item to include 12mm thick glass (clear/frosted) to be fixed as shown in mirror polish. T.W. runner should be melamine polished in matching colour of laminated etc complete in all respect.</p>				
<b>13.</b>	<p><b>Managers Table/Officer's Table</b> Providing and fixing in position manager's Table of size 6'-6" X 3'-6" as per drawing no. (6) / Officers Table of size 5' X 2'-6" as per drawing no (5) including side storage (credenza) by using 25mm thick plywood top and 18mm thick plywood for all other horizontal and vertical members. Telescopic CPU Stand/readymade keyboard tray shall be provided of approved model and make. Footrest made with T.W. member of size 4" X 1 1/2" finished with French polish.</p> <p>Side 'Storage ( Credenza ) as per drawing shall be provided. Facia of side Storage ( Credenza ) shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint. The side Storage ( credenza ) shall be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant /Bank</p> <p>All exposed plywood to be finished with 1mm thick laminate of approved make &amp; shade and all exposed edges of table top &amp; ply verticals to have 1" X 4" T.W. lipping. All exposed T.W. sections to be melaminated and internal surfaces to have white enamel paint as directed item to include plywood boxing all necessary hardware and fitting in Stainless Steel finish, lipping to all edge etc. complete in all respect.</p>	<p>Manager 6'6" X 3'</p> <p>Officer 5' X 2'6"</p>	<p>1no</p> <p>4no</p>		
<b>14</b>	<p><b>Staff Table</b> Providing and fixing in position Staff Table of size 4'6" X 2'6" as per drawing No. (5) by using 25mm thick plywood for top and 18mm thick plywood for all other horizontal and vertical member. Telescopic CPU Stand/ready made Keyboard tray shall be provided. Drawer unit as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished</p>				

	<p>with 1mm thick laminated and all other side shall be finished with white enamel paint. The drawer will be provided with handles (Stainless steel finish) and channel as per approval of the project Consultant/Bank. All exposed plywood surface to be finished with 1mm thick. Laminated of approved make and shade, and all exposed edges of table top and ply vertical to have 1”X1/4” T.W. lipping. All exposed T.W. sections to be melaminated and internal surface to have a white enamel paint as Directed. The items to include plywood boxing, All necessary hardware and fittings in stainless steel finish, lipping to all its edges etc.complete in all respects.</p>				
15	<p><b>Full height storage/ low Height Storage/ Back Storage (Credenza).</b>  Providing and fixing in position full height Storage/ Low Height Storage/ Back Storage ( Credenza) as shown in DRg.No.(8),(9) &amp; (10) respectively using plywood of required thickness finished with 1 mm thick laminated as shown in the Drawing and all other sides shall be finished with white enamel paint as details therein.  The storage units shall be provided with handles.  (Stainless Steel Finish) as per approval of the projects consultant/ Bank .  All exposed plywood surface to be finished with 1 mm thk .laminated of approved make &amp; shed and all exposed edges of plywood to have 1”x ¼ “ T.W. Lipping. All Exposed T.W. section to be melaminated in matching colour laminates and internal surface to have white enamel paint as directed. Item to include all necessary Hardware and Fitting in Stainless Steel finish, Godrej multipurpose locks including magnetic ball catcher etc. compete in all respect.</p>				
16.	<p><b>Side Table.</b>  For specification/size please contact with Architect.</p>	No.1			
17.	<p><b>Slip Counter.</b>  For specification/size please contact with Architect.</p>	1No 4ft	4 ft		
18.	<p><b>Sofa</b>  <b>3Seater</b>  <b>4 Seater</b></p>	No1 No.2	--		

<b>19.</b>	<b>Providing blinds to windows</b> For specification/size please contact with Architect.	Sq.ft	190		
<b>20.</b>	<b>Paneling of columns up to height of 8 ft.</b>	No 4	2 no		
<b>21.</b>	<b>TOTAL</b>				

**BANK OF INDIA****Murtizapur BRANCH.****QUOTAQTION DOCUMENT OF FURNISHING work finishing limit 10 days.**

<b>SR NO.</b>	<b>Description Of Item</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate (in Rs.)</b>	<b>Amount (in Rs.)</b>
<b>1</b>	<b>Flooring:</b> Providing and laying of 2'X2' Vitrified Tile flooring of approved make & shade viz. RAK (IMP-OFGY) of EURO (ATHENA) over necessary leveling screed of 1:4 cement mortar (20mm thick) with proper slope wherever required including pointing of the joints with white cement and matching pigments , curing etc. complete in all respects (excluding Toilets and Non – Customer area)	<b>Sq.ft</b>  <b>Vitrified ceramic</b>		<b>Rs.</b>  <b>Rs.</b>	
<b>2</b>	<b>Façade of Entrance Door-Refer Dwg.no.11</b> Providing and fixing in position Aluminum composite panel Boxing with PVDF coating & LDPE core laminated Eurobond / Altobond / Alukbond Exterior Grade 4 mm thick with composite of (0.5mm - 3mm-0.5mm)including fabrication for the same with aluminum fabrication for the same silicon sealent (Dow Corning 789) masking tape, necessary scaffolding etc. as detailed in drawing no. (11) Complete in all respects.	<b>Sq.ft.</b>	<b>90</b>		
<b>3</b>	<b>False ceiling (Armstrong)</b> Providing & fixing in position false ceiling in Armstrong 600X 600 mm X 15/16 mm Dune Supreme RH 99 Prima title with Tegular edge framework as specified by Armstrong Co. with suspender wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutout for diffusers and light feting, taping and finishing to proper & level, including making grooves and tapes doors for A.C. unit in 18 mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edge including finishing with White Plastic Emulsion Paint etc. complete in all respect. (Note:- Only the Plane area will be measured for payment. No extra payment will be made for cutouts, grooves, moulding etc.)	<b>Sq.ft.</b>	<b>1395</b>		

4.	<b>False Ceiling (Gypsum Board)</b> Providing & fixing in position false ceiling in Gypboard 12mm thick for horizontal & vertical fixed over G.I. framework as specified by India GypsmCo.Ltd. including trap door for A.C. unit in 18mm thick MR Grade plywood with Stainless Steel hinges & locks with moulding 1”x 1” for edge including finishing with white Plastic Emulation Paint etc. compete in all respect. (Note:- Only one plan area will be measures for payment. No extra payment will be made for cutouts, grooves, moulding etc.)	Sft.		--	
5	<b>Painting</b> Providing and applying White Plastic Emulation paint of Asian Paint/ICIDulux/Berger and Sporty Yellow-X 104 shade of Royal Luxury Emulsion of Asian Paint in minimum 2 coats including scraping, opening of existing cracks, filling up of “V” cracks with epoxy expandable putty ti required depths, making good weak plastered/unplastered surface with cement plaster wherever required. Item to include Plaster of Paris, primer, palti, and making good existing surface to receive new paint including cleaning on completion of painting work etc. complete in all respect.	Sq.ft  With Putty  With Putty		Rs.  Rs.	
6.	<b>Entrance Door</b> Proving and fixing Entrance Door (glazed) as per drawing no. 11 in Silver Anodisedaluminium door section (Jindal make) in top and bottom, glazed with 12mm thick glass of approved make with etching and frosting. Item to include floor springs, locks. All necessary hardware of Stainless Steel finished as approved by the project Consultant/Bank complete in all respects.	Sq.ft.	39		
7.	<b>Front Office Counter:</b> Proving and fixing in position Front Office Counter 2’-6” wide as per drawing No. (1-A,1_B, 1-C, 1-D & 15) comprising of the following complete in all respects:- xii) Working top made with 25 mm thick plywood finished with 1 mm thick laminated. Outside edge of the working top shall be provided with 1 1/4X1” .teak wood moulding finished with melamine polish.	Rft	16.’0”		

	<p>Inside edge will be provided with ½ “X1” T.W. beading putti with melamine finish.</p> <p>xiii) Vertical facia (Apron) made with 18 mm thick plywood finished with 1mm thick laminated with 1 mm thick grooves at the joint of laminates of two different shade.</p> <p>xiv) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18mm thick laminated with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shade of laminates.</p> <p>xv) Glazed partition above working top to be provided with 12mm thick clear glass cut to be standard shape fixed to the partition as per fixing detail and boxing with concealed S,S, finished ‘D’ bracket as shown in the drawing. The exposed edge of the glass shall be finished in mirror polish.</p> <p>xvi) 3’-10’ high Boxing (10:X10”) made with 18 mm thick plywood finished with 1 mm thick laminated including providing and fixing 6 mm thick square frosted glass at the height 3’-2” above finished floor level.</p> <p>xvii) 1’-9” high Boxing (5”X5”) made with 12 mm thick plywood finished with 1mm thick laminated.</p> <p>xviii) Vertical support made with 18 mm thick plywood fished with white enamel paint.</p> <p>xix) Telescopic CPU Stand/ready made Keyboard tray shall be provided all approved model and make.</p> <p>xx) Footrest made with T.W. member of size 4”X1 ½ “ finished French polish .</p> <p>xxi) Drawer unit as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1 mm thick limited and all</p>				
--	---	--	--	--	--

	<p>other side shall be finished with white enamel paint. The drawer will provided with handles (Stainless Still finish) and channel as per approval of the project consultant/Bank.</p> <p>xxii) Boxing as per drawing made with 12mm thick plywood finished with synthetic enamel paint shall be provided below the table top for the LAN cabling/Telephone wire conducting.</p> <p>The item to include all necessary hardware and fitting in Stainless still finish, lipping to all the edge and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"X10' boxing as shown in the drawing. Necessary beading with melamine polish for fixing the glass are to be provided.</p>				
8.	<p><b>Cash Counter;</b>  Providing and fixing in the position Cash Counter 2'-9" wide as per drawing No. (2-A., 2-B, 2-C, 2-D, 2-E, 2-F) comprising of the following:</p> <p>vii) Working top made with 25 mm thick plywood finish with 1 mm thick laminated. Outside edge of the working top shall be provided with melamine polish. Inside edge will be provided with ½"X1" T.W. beading patti with melamine polish.</p> <p>viii) Vertical facia (Apron) made wiyh 18mm thick plywood finish with 1mm thick laminated with 1mm thick groove at the joint of laminated of two different shade.</p> <p>ix) Vertical drop (horizontal band) shall be provided on the fecia below the working top made with 18b mm thick plywood finish 1mm thick laminated with provision for concealed light, 1mm thick groove shall be provided at the joint of two different shade of laminated.</p> <p>x) Glazed partition 1'-4" height above working top provided with 12mm thick toughened and frosted</p>	Rft	11"0"		

	<p>glass beside non-transparent film from inside foxed to partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in the drawing. The exposed edged of the glass shall be finish in mirror polish.</p> <p>xi) Transaction top shall be provided with 12mm thick toughened glass (partly glazed partly frosted) fixed horizontally with concealed stainless still D bracket, both exposed edge (inside and outside) shall be moulded and finished in the mirror polish.</p> <p>xii) Glazed partition having height 1.0" above the transaction top (in facia) shall be provided with 12mm thick glass (clear) with cut out of 8"X4"as per drawing. The edge cut out and the top edge of the glass are to be mirror polished and to be fixed to be partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in .</p> <p>Glass (clear) above the sit to be fixed to partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in the drawing. The exposed edge shall be finished in mirror polish.</p> <p>vii)7'-7" high Boxing (10'X10") made with 8mm thick plywood as per drawing with 1-6" horizontal extension at the top including providing and fixing 6mm thick square frosted glass at the height of 5"-11' above finished floor level.</p> <p>xiv) 1'-9' high boxing (5"X5") made with 12mm thick plywood finished with 1mm thick laminated aer to be provided.</p> <p>xv) Telescopic CPU Stand/ready made Keyboard tray shall be provided all approved model and make.</p> <p>xvi) footrest made with T.W. member of size 4'X1 1/2"finished with French polish.</p> <p>xvii) Drawer unit as per drawing shall be provided and each drawer should have vertical partition for</p>				
--	---	--	--	--	--

	<p>keeping currency notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with white enamel paint. The drawer will be provided with handles (Stainless Steel finished) and channels as per approval of the Project Consultant/Bank .</p> <p>xviii) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.</p> <p>The item to include all necessary hardware and fitting in Stainless Steel finish, lapping to all edge and making provision only for electrical fitting behind the Vertical drop and also in the 10”X10” boxing as shown in the drawing . necessary beading with matching melamine polish for fixing the glass are to be provided as per drawing/as directed.</p>				
<b>9.</b>	<p><b>Solid Full Height Partition</b>  Providing and fixing in opposition solid full Height Partition in frame work including door in the 2’X2’ grid (horizontally and vertically) comprising of 2”X1 1/2” T.W. section with 6mm thick plywood on the both side finished with 1mm thick laminated of the approved make and color as shown in drawing No. 17. item to include 2”X2” T.W. member for door frame. All exposed T.W. surface to be finish in melamine polish of the matching laminated color as directed including all necessary Stainless Still finish fitting/hardware, door closers, Godrej locks, and wood preservative paint etc. as per list of approved by the Project consultace/Bank complete in all respect.  (Note: In case fall ceiling, the vertical T.W. member to be fixed with pucca ceiling but the area of partition payable will be below the fall ceiling only).</p>	Sq.ft			
<b>10.</b>	<p><b>Partly Gazed full Height partition</b>  Providing and fixing in position partly glazed Full Height Partition work as show in the drawing nos. (3) &amp; (4) including door as</p>	Sq.ft	325		

	<p>shown in the drawing No. (13) in frame work at 2'X2' grid (Horizontally and Vertically) compromising of 2"X1 1/2" T.W. section and/or as per frame work show in the drawing with 6mm plywood on the both side finishing with 1mm thick laminated of approved shade and color as shown in the drawing. Item to include 8mm thick glass with etching and frosting as per design and 2"X2" T,W. member for door frame to take 8mm thick glass with etching and frosting. All exposed T.W. surface to be finished in melamine polish of matching laminated color as directed including all necessary Stainless Steel finish fitting/hardware, door closer, Godrej locks wood preservative paint etc. as per list of approved material and as approved by the project Consultance/Bank complete in all respect. (Note: in case of false ceiling, the vertical T.W. member to be fixed with pucca ceiling but the area of partition payable will be below the fall ceiling only).</p>				
<p><b>11.</b></p>	<p><b>Party Glazed Partition for Cash Cabins</b> Providing and fixing in the position 7'-7" high partly glazed partition for cash Cabins as per drawing nos. (2-A,2-B,2-C,2-D&amp;2-E) including door drawing no. (12) in frame work at 2'X2' grid (horizontally and vertically) compromising of 2"X1 1/2" T.W. section and/or as per frame work show in the drawing with 6mm plywood on the both side finishing with 1mm thick laminated of approved shade and color as shown in the drawing. Item to 8mm thick glass with etching and frosting as per design and 2"X2" T,W. member for door frame to take 8mm thick glass with etching and frosting. The door will be provided with T.W. louvers finished in melamine polish of matching laminated color. The door are also to be provided with Godrej Night Latch. Two wooden trays are also to be provided as per drawing. Necessary cuttuos are to be provided in the glass and the edge of the glass cuttuos are to be finished in mirror polish. All exposed T.W. surface to be finished in melamine polish of matching laminated color as directed including all necessary</p>	<p>Sq.ft.</p>	<p>298</p>		

	Stainless steel Finifhfitng/hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the project Consultant/Bank complete in all respect.				
<b>12.</b>	<b>Partly Glazed Low Height Partition</b> Providing and fixing in position partly glazed low height partition (21?2” thick) in frame work with T.W. vertical member at 2” c/c and 3 horizontal member at equal distance comprising of 2”X1 1/2”T.W. section with 6mm plywood on both side finish with 1mm thick laminated of the approved make and shade as shown in drawing no. (14)or(3). Item to include 12mm thick glass (clear/frosted) to be fixed as shown in mirror polish. T.W. runner should be melamine polished in matching colour of laminated etc complete in all respect.	Sq.ft	90		
<b>13.</b>	<b>Managers Table/Officer’s Table</b> Providing and fixing in position manager’s Table of size 6’-6”X3’-0”as per drawing no.(6)/Officers Table of size 5’X2’-6” as per drawing no (5)including side storage (credenza) by sung 25mm thick plywood top and 18mm thick plywood for all other horizontal and vertical members. Telescopic CPU Stand/ready made keyboard tray shall be provided of approved model and make. footrest made with T.W> member of size 4”X1 1/2” finished with French polish.  Side ‘Storage ( Credenza ) as per drawing shall be provided. Facia of side Storage ( Credenza ) shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint. The side Storage (credenza) shall be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant /Bank  All exposed plywood to be finished with 1mm thick laminate of approved make & shade and all exposed edges of table top & ply verticals to have 1”x4” T.W. lipping. All exposed T.W.sections to be melaminated and	Manager 6’6”x3’  Officer 5’x2’6”	1no  5no		

	<p>internal surfaces to have white enamel paint as directed item to include plywood boxing all necessary hardware and fitting in Stainless Steel finish, lipping to all edge etc. complete in all respect.</p>				
14	<p><b>Staff Table</b>  Providing and fixing in position Staff Table of size 4'6"X2' 6" as per drawing No. (5) by using 25mm thick plywood for top and 18mm thick plywood for all other horizontal and vertical member. Telescopic CPU Stand/ready made Keyboard tray shall be provided.  Drawer unit as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1mm thick laminated and all other side shall be finished with white enamel paint. The drawer will be provided with handles (Stainless steel finish) and channel as per approval of the project Consultant/Bank.  All exposed plywood surface to be finished with 1mm thick. Laminated of approved make and shade, and all exposed edges of table top and ply vertical to have 1"X1/4" T.W. lipping. All exposed T.W. sections to be melaminated and internal surface to have a white enamel paint as Directed. The items to include plywood boxing, All necessary hardware and fittings in stainless steel finish, lipping to all its edges etc.complete in all respects.</p>				
15	<p><b>Full height storage/ low Height Storage/ Back Storage (Credenza).</b>  Providing and fixing in position full height Storage/ Low Height Storage/ Back Storage ( Credenza) as shown in DRg.No.(8),(9) &amp; (10) respectively using plywood of required thickness finished with 1 mm thick laminated as shown in the Drawing and all other sides shall be finished with white enamel paint as details therein.  The storage units shall be provided with handles.  (Stainless Steel Finish) as per approval of the projects consultant/ Bank .  All exposed plywood surface to be finished with 1 mm thk .laminated of approved make</p>				

	& shed and all exposed edges of plywood to have 1”x ¼ “ T.W. Lipping. All Exposed T.W. section to be melaminated in matching colour laminates and internal surface to have white enamel paint as directed. Item to include all necessary Hardware and Fitting in Stainless Steel finish, Godrej multipurpose locks including magnetic ball catcher etc. compete in all respect.				
<b>16.</b>	<b>Side Table.</b> For specification/size please contact with Architect.	No.1			
<b>17.</b>	<b>Slip Counter.</b> For specification/size please contact with Architect.	1No 4ft	1No		
<b>18.</b>	<b>Sofa</b> <b>3Seater</b> <b>4 Seater</b>	No 1 No 1			
<b>19.</b>	<b>Providing blinds to windows</b> For specification/size please contact with Architect.	Sq.ft	216		
<b>20.</b>	<b>Paneling of columns up to height of 8 ft.</b>	No	9		
<b>21.</b>	<b>TOTAL</b>				

**BANK OF INDIA**

**Nandura BRANCH.**

**QUOTAQTION DOCUMENT OF FURNISHING work finishing limit 10 days.**

<b>SR NO.</b>	<b>Description Of Item</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate (inRs.)</b>	<b>Amount (in Rs.)</b>
<b>1</b>	<p><b>Flooring:</b>                      Providing and laying of 2'X2' Vitrified Tile flooring of approved make &amp; shade viz. RAK (IMP-OFGY) of EURO (ATHENA) over necessary leveling screed of 1:4 cement mortar (20mm thick) with proper slope wherever required including pointing of the joints with white cement and matching pigments , curing etc. complete in all respects (excluding Toilets and Non – Customer area)</p>	<p><b>Sq.ft</b>          <b>Vitrified ceramic</b></p>		<p><b>Rs.</b>          <b>Rs.</b></p>	
<b>2</b>	<p><b>Façade of Entrance Door-Refer Dwg.no.11</b>                      Providing and fixing in position Aluminum composite panel Boxing with PVDF coating &amp; LDPE core laminated Eurobond / Altobond / Alukbond Exterior Grade 4 mm thick with composite of (0.5mm - 3mm-0.5mm)including fabrication for the same with aluminum fabrication for the same silicon sealent (Dow Corning 789) masking tape, necessary scaffolding etc. as detailed in drawing no. (11) Complete in all respects.</p>	<b>Sq.ft.</b>	<b>90</b>		
<b>3</b>	<p><b>False ceiling (Armstrong)</b>                      Providing &amp; fixing in position false ceiling in Armstrong 600X 600 mm X 15/16 mm Dune Supreme RH 99 Prima title with Tegular edge framework as specified by Armstrong Co. with suspender wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutout for diffusers and light feting, taping and finishing to proper &amp; level, including making grooves and tapes doors for A.C. unit in 18 mm thick M.R. Grade Plywood with Stainless Steel hinges &amp; locks with moulding 1" x 1" for edge including finishing with White Plastic Emulsion Paint etc. complete in all respect. (Note:- Only the Plane area will be measured for payment. No extra payment will be made for cutouts, grooves, moulding etc.)</p>	<b>Sq.ft.</b>	<b>1229</b>		

4.	<b>False Ceiling (Gypsum Board)</b> Providing & fixing in position false ceiling in Gypboard 12mm thick for horizontal & vertical fixed over G.I. framework as specified by India GypsmCo.Ltd. including trap door for A.C. unit in 18mm thick MR Grade plywood with Stainless Steel hinges & locks with moulding 1”x 1” for edge including finishing with white Plastic Emulation Paint etc. compete in all respect. (Note:- Only one plan area will be measures for payment. No extra payment will be made for cutouts, grooves, moulding etc.)	<b>Sft.</b>		--	
5	<b>Painting</b> Providing and applying White Plastic Emulation paint of Asian Paint/ICIDulux/Berger and Sporty Yellow-X 104 shade of Royal Luxury Emulsion of Asian Paint in minimum 2 coats including scraping, opening of existing cracks, filling up of “V” cracks with epoxy expandable putty ti required depths, making good weak plastered/unplastered surface with cement plaster wherever required. Item to include Plaster of Paris, primer, palti, and making good existing surface to receive new paint including cleaning on completion of painting work etc. complete in all respect.	Sq.ft  With Putty  With Putty		Rs.  Rs.	
6.	<b>Entrance Door</b> Proving and fixing Entrance Door (glazed) as per drawing no. 11 in Silver Anodisedaluminium door section (Jindal make) in top and bottom, glazed with 12mm thick glass of approved make with etching and frosting. Item to include floor springs, locks. All necessary hardware of Stainless Steel finished as approved by the project Consultant/Bank complete in all respects.	Sq.ft.	39		
7.	<b>Front Office Counter:</b> Proving and fixing in position Front Office Counter 2’-6” wide as per drawing No. (1-A,1_B, 1-C, 1-D & 15) comprising of the following complete in all respects:- xxiii) Working top made with 25 mm thick plywood finished with 1 mm thick laminated. Outside edge of the working top shall be provided with 11/4X1” .teak wood	Rft	15.’3”		

	<p>moulding finished with melamine polish. Inside edge will be provided with ½ “X1” T.W. beading putti with melamine finish.</p> <p>xxiv) Vertical facia (Apron) made with 18 mm thick plywood finished with 1mm thick laminated with 1 mm thick grooves at the joint of laminates of two different shade.</p> <p>xxv) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18mm thick laminated with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shade of laminates.</p> <p>xxvi) Glazed partition above working top to be provided with 12mm thick clear glass cut to be standard shape fixed to the partition as per fixing detail and boxing with concealed S,S, finished ‘D’ bracket as shown in the drawing. The exposed edge of the glass shall be finished in mirror polish.</p> <p>xxvii) 3’-10’ high Boxing (10:X10”) made with 18 mm thick plywood finished with 1 mm thick laminated including providing and fixing 6 mm thick square frosted glass at the height 3’-2” above finished floor level.</p> <p>xxviii) 1’-9” high Boxing (5”X5”) made with 12 mm thick plywood finished with 1mm thick laminated.</p> <p>xxix) Vertical support made with 18 mm thick plywood fished with white enamel paint.</p> <p>xxx) Telescopic CPU Stand/ready made Keyboard tray shall be provided all approved model and make.</p> <p>xxxii) Footrest made with T.W. member of size 4”X1 ½ “ finished French polish .</p> <p>xxxiii) Drawer unit as per drawing shall be provided with multipurpose</p>				
--	--	--	--	--	--

	<p>Godrej locks in each drawer. Facia of drawer unit shall be finished with 1 mm thick limited and all other side shall be finished with white enamel paint. The drawer will provided with handles (Stainless Still finish) and channel as per approval of the project consultant/Bank.</p> <p>xxxiii) Boxing as per drawing made with 12mm thick plywood finished with synthetic enamel paint shall be provided below the table top for the LAN cabling/Telephone wire conducting.</p> <p>The item to include all necessary hardware and fitting in Stainless still finish, lipping to all the edge and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"X10' boxing as shown in the drawing. Necessary beading with melamine polish for fixing the glass are to be provided.</p>				
8.	<p><b>Cash Counter;</b> Providing and fixing in the position Cash Counter 2'-9" wide as per drawing No. (2-A., 2-B, 2-C, 2-D, 2-E, 2-F) comprising of the following:</p> <p>xiii) Working top made with 25 mm thick plywood finish with 1 mm thick laminated. Outside edge of the working top shall be provided with melamine polish. Inside edge will be provided with ½"X1" T.W. beading patti with melamine polish.</p> <p>xiv) Vertical facia (Apron) made wiyh 18mm thick plywood finish with 1mm thick laminated with 1mm thick groove at the joint of laminated of two different shade.</p> <p>xv) Vertical drop (horizontal band) shall be provided on the fecia below the working top made with 18b mm thick plywood finish 1mm thick laminated with provision for concealed light, 1mm thick groove shall be provided at the joint of two different shade of laminated.</p>	Rft	11"0"		

	<p>xvi) Glazed partition 1'-4" height above working top provided with 12mm thick toughened and frosted glass beside non-transparent film from inside fixed to partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in the drawing. The exposed edge of the glass shall be finish in mirror polish.</p> <p>xvii) Transaction top shall be provided with 12mm thick toughened glass (partly glazed partly frosted) fixed horizontally with concealed stainless steel D bracket, both exposed edge (inside and outside) shall be moulded and finished in the mirror polish.</p> <p>xviii) Glazed partition having height 1.0" above the transaction top (in facia) shall be provided with 12mm thick glass (clear) with cut out of 8"X4" as per drawing. The edge cut out and the top edge of the glass are to be mirror polished and to be fixed to be partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in .</p> <p>Glass (clear) above the sit to be fixed to partition as per fixing detail and to boxing with concealed S.S. finished 'D' bracket as shown in the drawing. The exposed edge shall be finished in mirror polish.</p> <p>vii) 7'-7" high Boxing (10'X10") made with 8mm thick plywood as per drawing with 1-6" horizontal extension at the top including providing and fixing 6mm thick square frosted glass at the height of 5'-11' above finished floor level.</p> <p>xix) 1'-9' high boxing (5"X5") made with 12mm thick plywood finished with 1mm thick laminated aer to be provided.</p> <p>xx) Telescopic CPU Stand/ready made Keyboard tray shall be provided all approved model and make.</p>				
--	--	--	--	--	--

	<p>xxi) footrest made with T.W. member of size 4'X1 1/2" finished with French polish.</p> <p>xxii) Drawer unit as per drawing shall be provided and each drawer should have vertical partition for keeping currency notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with white enamel paint. The drawer will be provided with handles (Stainless Steel finished) and channels as per approval of the Project Consultant/Bank .</p> <p>xxiii) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.</p> <p>The item to include all necessary hardware and fitting in Stainless Steel finish, lapping to all edge and making provision only for electrical fitting behind the Vertical drop and also in the 10"X10" boxing as shown in the drawing . necessary beading with matching melamine polish for fixing the glass are to be provided as per drawing/as directed.</p>				
<p><b>9.</b></p>	<p><b>Solid Full Height Partition</b>  Providing and fixing in opposition solid full Height Partition in frame work including door in the 2'X2' grid (horizontally and vertically) comprising of 2"X1 1/2" T.W. section with 6mm thick plywood on the both side finished with 1mm thick laminated of the approved make and color as shown in drawing No. 17. item to include 2"X2" T.W. member for door frame. All exposed T.W. surface to be finish in melamine polish of the matching laminated color as directed including all necessary Stainless Still finish fitting/hardware, door closers, Godrej locks, and wood preservative paint etc. as per list of approved by the Project consultace/Bank complete in all respect.  (Note: In case fall ceiling, the vertical T.W.</p>	<p>Sq.ft</p>			

	member to be fixed with pucca ceiling but the area of partition payable will be below the fall ceiling only).				
<b>10.</b>	<p><b>Partly Gazed full Height partition</b>  Providing and fixing in position partly glazed Full Height Partition work as show in the drawing nos. (3) &amp; (4) including door as shown in the drawing No. (13) in frame work at 2'X2' grid (Horizontally and Vertically) compromising of 2"X1 1/2" T.W. section and/or as per frame work show in the drawing with 6mm plywood on the both side finishing with 1mm thick laminated of approved shade and color as shown in the drawing. Item to include 8mm thick glass with etching and frosting as per design and 2"X2" T,W. member for door frame to take 8mm thick glass with etching and frosting.  All exposed T.W. surface to be finished in melamine polish of matching laminated color as directed including all necessary Stainless Steel finish fitting/hardware, door closer, Godrej locks wood preservative paint etc. as per list of approved material and as approved by the project Consultance/Bank complete in all respect. (Note: in case of false ceiling, the vertical T.W. member to be fixed with pucca ceiling but the area of partition payable will be below the fall ceiling only).</p>	Sq.ft	298		
<b>11.</b>	<p><b>Party Glazed Partition for Cash Cabins</b>  Providing and fixing in the position 7'-7" high partly glazed partition for cash Cabins as per drawing nos. (2-A,2-B,2-C,2-D&amp;2-E) including door drawing no. (12) in frame work at 2'X2' grid (horizontally and vertically) compromising of 2"X1 1/2" T.W. section and/or as per frame work show in the drawing with 6mm plywood on the both side finishing with 1mm thick laminated of approved shade and color as shown in the drawing. Item to 8mm thick glass with etching and frosting as per design and 2"X2" T,W. member for door frame to take 8mm thick glass with etching and frosting. The door will be provided with T.W. louvers finished in melamine polish of matching laminated color. The door are also to be provided with Godrej Night</p>	Sq.ft.	230		

	<p>Latch. Two wooden trays are also to be provided as per drawing. Necessary cutouts are to be provided in the glass and the edge of the glass cutouts are to be finished in mirror polish.</p> <p>All exposed T.W. surface to be finished in melamine polish of matching laminated color as directed including all necessary Stainless steel Finishing/hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the project Consultant/Bank complete in all respect.</p>				
12.	<p><b>Partly Glazed Low Height Partition</b>  Providing and fixing in position partly glazed low height partition (21/2" thick) in frame work with T.W. vertical member at 2" c/c and 3 horizontal member at equal distance comprising of 2"X1 1/2" T.W. section with 6mm plywood on both side finish with 1mm thick laminated of the approved make and shade as shown in drawing no. (14) or (3). Item to include 12mm thick glass (clear/frosted) to be fixed as shown in mirror polish. T.W. runner should be melamine polished in matching colour of laminated etc complete in all respect.</p>	Sq.ft	82		
13.	<p><b>Managers Table/Officer's Table</b>  Providing and fixing in position manager's Table of size 6'-6" X 3'-0" as per drawing no.(6)/Officers Table of size 5' X 2'-6" as per drawing no (5) including side storage (credenza) by using 25mm thick plywood top and 18mm thick plywood for all other horizontal and vertical members.  Telescopic CPU Stand/ready made keyboard tray shall be provided of approved model and make. footrest made with T.W&gt; member of size 4" X 1 1/2" finished with French polish.</p> <p>Side 'Storage ( Credenza ) as per drawing shall be provided. Facia of side Storage ( Credenza ) shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with</p>	<p>Manager 6'6"x3'</p> <p>Officer 5'x2'6"</p>	<p>1no</p> <p>4no</p>		

	<p>white enamel paint. The side Storage (credenza) shall be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant /Bank</p> <p>All exposed plywood to be finished with 1mm thick laminate of approved make &amp; shade and all exposed edges of table top &amp; ply verticals to have 1"x4" T.W. lipping. All exposed T.W.sections to be melaminated and internal surfaces to have white enamel paint as directed item to include plywood boxing all necessary hardware and fitting in Stainless Steel finish, lipping to all edge etc. complete in all respect.</p>				
14	<p><b>Staff Table</b>  Providing and fixing in position Staff Table of size 4'6"X2' 6" as per drawing No. (5) by using 25mm thick plywood for top and 18mm thick plywood for all other horizontal and vertical member. Telescopic CPU Stand/ready made Keyboard tray shall be provided.  Drawer unit as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1mm thick laminated and all other side shall be finished with white enamel paint. The drawer will be provided with handles (Stainless steel finish) and channel as per approval of the project Consultant/Bank.  All exposed plywood surface to be finished with 1mm thick. Laminated of approved make and shade, and all exposed edges of table top and ply vertical to have 1"x1/4" T.W. lipping. All exposed T.W. sections to be melaminated and internal surface to have a white enamel paint as Directed. The items to include plywood boxing, All necessary hardware and fittings in stainless steel finish, lipping to all its edges etc.complete in all respects.</p>				
15	<p><b>Full height storage/ low Height Storage/ Back Storage (Credenza).</b>  Providing and fixing in position full height Storage/ Low Height Storage/ Back Storage ( Credenza) as shown in DRg.No.(8),(9) &amp; (10) respectively using plywood of required</p>				

	<p>thickness finished with 1 mm thick laminated as shown in the Drawing and all other sides shall be finished with white enamel paint as details therein.</p> <p>The storage units shall be provided with handles.</p> <p>(Stainless Steel Finish) as per approval of the projects consultant/ Bank .</p> <p>All exposed plywood surface to be finished with 1 mm thk .laminated of approved make &amp; shed and all exposed edges of plywood to have 1”x ¼ “ T.W. Lipping. All Exposed T.W. section to be melaminated in matching colour laminates and internal surface to have white enamel paint as directed. Item to include all necessary Hardware and Fitting in Stainless Steel finish, Godrej multipurpose locks including magnetic ball catcher etc. compete in all respect.</p>				
<b>16.</b>	<b>Side Table.</b> For specification/size please contact with Architect.	No.1			
<b>17.</b>	<b>Slip Counter.</b> For specification/size please contact with Architect.	1No 4ft	1No		
<b>18.</b>	<b>Sofa</b> <b>3Seater</b> <b>4 Seater</b>	No 1 No 1			
<b>19.</b>	<b>Providing blinds to windows</b> For specification/size please contact with Architect.	Sq.ft	151		
<b>20.</b>	<b>Paneling of columns up to height of 8 ft.</b>	No	4		
<b>21.</b>	<b>TOTAL</b>				

## **NAGPUR ZONE –II**

### **SPECIAL TERMS AND CONDITIONS**

1. The prospective bidder is advised to visit site to get him acquainted with the site conditions, prior to submitting his bid.
2. The prices quoted should be inclusive of all taxes & duties, as applicable on date. No extra payment will be released under any pretext what so ever in this regard.
3. The prices quoted should be inclusive of freight, handling, unloading at site in Banks' premises at Achalpur, Nandura & Murtizapur Branch.
4. Octroi charges as per NMC's present rates will be deemed to have been included in the offered prices. No Octroi exemption certificate & / Or extra payment will be released in this regard.
5. The rates offered will be inclusive of labor charges for handling, installation, testing, commissioning & giving test & Trial to the satisfaction of the Banks' officer/consultant appointed by the Bank.
6. Statutory permissions, preparation & approval of drawing by the electrical inspector & approval of installation by him, prior to commissioning will be the contractors' responsibility & no extra payment will be made to the contractor on this account. However payment of Government's fee in this regard will be released to the contractor against production of relevant document, or it may be paid by he Bank directly to the department by cheque.
7. All the work of transfer of power connections from the existing DB to new DB will be carried out on Sunday or any non working day, so that the day to day works of the Banks is not hampered.
8. Official charges of MSEDCL foe meter shifting shall be paid by the Bank against MSEDL's demand note. However day to day follow up for getting the demand note & charging the supply after shifting shall be the contractor's responsibility.

#### **NOTICE TO TENDERERS :**

1. Sealed quotations should be addressed to The Zonal Manager, Bank of India, Zonal Office 2<sup>nd</sup> Floor, Nagpur and super-scribed as Quotation for Interior Furniture Work at Achalpur, Nandura & Murtizapur Branch Nagpur and sent as to reach the office of The Zonal Manager, Bank of India., Zonal Office, 2<sup>nd</sup> Floor Nagpur not later than 12.00 PM on 11 / 02 / 2012
2. Quotations shall be opened at the office of Zonal Manager, Bank of India, Zonal Office, 2<sup>nd</sup> Floor Nagpur on the 13 / 02 / 2012 at 5.00 PM. The rates quoted shall be valid for 90 days from the date of opening,
3. The Zonal Manager ,Bank of India, Zonal Office, 2<sup>nd</sup> Floor, Nagpur does not bind himself to accept the lowest or any quotation and reserves the right to accept or reject any or all the quotations whether in whole or in part without assigning any reason for doing so. The Bank reserves the right to negotiate with the lowest quotations/s .
4. Within seven days of the receipt of intimation from the owner of acceptance of his/their quotation, the successful tenderer shall be bound to implement the contract by signing the agreement in accordance with the draft agreement and the conditions of contract with the owner.
5. The rates quoted by the contractor should include all charges for scaffolding, materials, labor, hire for any tools, marking out and clearing of the site as mentioned in the specifications. The rate quoted by the tenderer will be deemed to be for the finished work to be measured at site. The rates shall be inclusive of all applicable taxes, sales tax, octroi duty, works contract tax Provident Fund, Insurance etc. levied by any Government or any public

body. The contractor shall abide by the rules of Minimum Wages Act and child Labor act and keep the Bank indemnified regarding the same.

6. The rate shall be binding to the Contractor for all the tender items till the completion of the work irrespective of variation in market rates of material and labor.

7. Special attention of the tenderer is drawn to the alternative items in the schedule of quantities. The rates and amount for these alternative items. If any, shall be duly filled in. The Bank reserves the right to adopt any of the alternative items, after scrutinizing and deciding upon the tenders or later when the work is being executed.

8. The successful tenderer should make own arrangement to obtain all materials required for the work.

9. The various materials stored on site shall be protected from the fire or rains etc. and the contractor shall be responsible for any damage caused to the Bank for the same.

10. The contractor shall allow enough facilities to the sub-contractors employed by the Bank and should co-operate with them and that small holes etc. made by these sub-contractors to the structure shall be properly corrected by the general contractor without any prejudice and extra cost whatsoever.

11. The Bank reserves the right to omit any item or items or part thereof while execution of the work for which contractor shall not claim any compensation whatsoever.

12. The contractor will have to follow the instructions and guidelines as issued to him by the Bank. If any work is not carried out satisfactory or to the required standard in the opinion of architect/Bank the contractor will have to rectify it again at his own cost, without any additional payment and without any challenge.

I/We hereby declare that I/We have read and understood the above instructions for the guidance of the tenderer.

Date:

Seal

Signature & Stamp of the  
Tenderer

To,  
The Zonal Manager,  
Bank of India  
Zonal Office 2<sup>nd</sup> Floor,  
S.V.PatelMarg, Kingsway  
Nagpur Zone-II, Nagpur

From :

-----

-----

-----

**Sub – Tender for the Interior Furniture Work at Achalpur,Nandura & Murtizapur Branches.**

Dear Sir,

With reference to the tender invited by you for above mentioned work, I/We hereby offer to execute the work. I/w e have examined and studied carefully all the drawings, specifications, conditions of contract, site and agree to comply with them, I/we agree to complete the whole work within the stipulated time from the date of work order. I/We are aware that any of items/s can be cancelled or replaced and quantity of any of items can be increased or decreased at any time by the Architect OR Bank, for which I/We shall not claim extra.

Yours Faithfully

Contractors' Signature  
(with stamp & Address)